

MERRIMACK RIVER BASIN
MANCHESTER, NEW HAMPSHIRE

**MASSABESIC LAKE DAM
NH 00103**

**PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM**



The original hardcopy version of this report
contains color photographs and/or drawings.
For additional information on this report
please email

U.S. Army Corps of Engineers
New England District
Email: Library@nae02.usace.army.mil

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

AUGUST 1978

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| REPORT DOCUMENTATION PAGE | | READ INSTRUCTIONS BEFORE COMPLETING FORM |
|---|-----------------------|---|
| 1. REPORT NUMBER NH 000103 | 2. GOVT ACCESSION NO. | 3. RECIPIENT'S CATALOG NUMBER |
| 4. TITLE (and Subtitle) Massabesic Lake Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS | | 5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT |
| 7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION | | 6. PERFORMING ORG. REPORT NUMBER |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS | | 8. CONTRACT OR GRANT NUMBER(s) |
| 1. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254 | | 10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS |
| 14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) | | 12. REPORT DATE August 1978 |
| | | 13. NUMBER OF PAGES 45 |
| | | 15. SECURITY CLASS. (of this report) UNCLASSIFIED |
| | | 15a. DECLASSIFICATION/DOWNGRADING SCHEDULE |
| 6. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED | | |
| 7. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) | | |
| 8. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report. | | |
| 9. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Merrimack River Basin Manchester, New Hampshire Cohas Brook | | |
| 10. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is a large concrete and stone masonry dam with earth embankments. The overall length is about 500 ft. with a maximum height of 27 ft. The dam is assessed to be in poor condition. Problems include structural cracking of an unknown origin, embankment seepage, and low spillway capacity. A test flood of 23,700 cfs inflow into the reservoir would overtop the dam by about 3.2 ft. | | |



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02154

REPLY TO
ATTENTION OF:
NEDED

AUG 21 1979

Honorable Hugh J. Gallen
Governor of the State of New Hampshire
State House
Concord, New Hampshire 03301

Dear Governor Gallen:

I am forwarding to you a copy of the Massabesic Lake Dam Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Water Resources Board, the cooperating agency for the State of New Hampshire. In addition, a copy of the report has also been furnished the owner, Manchester Water Works, 281 Lincoln Street, Manchester, New Hampshire 03301.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Water Resources Board for your cooperation in carrying out this program.

Sincerely yours,

WILLIAM E. HODGSON, JR.
Colonel, Corps of Engineers
Acting Division Engineer

Incl
As stated

MASSABESIC LAKE DAM

NH 00103

MERRIMACK RIVER BASIN
MANCHESTER, NEW HAMPSHIRE

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

PHASE I REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam Massabesic Lake Dam
State Located New Hampshire
County Located Hillsborough
City or Town Manchester
Stream Cohas Brook
Date of Inspection 6/12/78 and 7/5/78

Brief Assessment


Massabesic Lake Dam is a large concrete and stone masonry dam with earth embankments. Overall length is about 500 feet and maximum height is 27 feet. The dam was constructed in 1873 and no records of design and construction are known to exist. The dam regulates the outflow of Massabesic Lake, operated as water supply by the City of Manchester. The dam is assessed to be in the high hazard classification.

Massabesic Lake Dam is assessed to be in overall poor condition. Problems include structural cracking of an unknown origin, embankment seepage, and low spillway capacity.

A test flood (equal to the probable maximum flood) of 23,700 cfs inflow into the reservoir would overtop the dam by about 3.2 feet. Spillway capacity is about 24% of the test flood outflow. If the existing flashboards were replaced with properly designed flashboards, the spillway capacity would increase to about 37% of the test flood outflow, and the overtopping height would drop to about 1.7 feet.


Recommendations include obtaining professional advice on (1) the cause of the spillway structural cracking, (2) decreasing flood vulnerability, and (3) repairing the seepages uncovered. Action is also recommended on other less serious matters. The owner should carry out the recommendations and remedial measures within 12 months after receipt of this Phase I Report.

WHITMAN & HOWARD, INC.



T T Chiang

T. T. Chiang, Ph.D., P.E.



John L. Scott

John L. Scott, P.E.

This Phase I Inspection Report on Massabesic Lake Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.



CHARLES G. TIERSCH, Chairman
Chief, Foundation and Materials Branch
Engineering Division




FRED J. RAVENS, Jr., Member
Chief, Design Branch
Engineering Division



SAUL COOPER, Member
Chief, Water Control Branch
Engineering Division

APPROVAL RECOMMENDED:



JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established guidelines, the spillway test flood is based on the estimated "Probably Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a high inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

TABLE OF CONTENTS


| | <u>Page</u> |
|--|-------------|
| LETTER OF TRANSMITTAL | |
| BRIEF ASSESSMENT | i |
| REVIEW BOARD PAGE | iii |
| PREFACE | iv |
| TABLE OF CONTENTS | v |
| OVERVIEW PHOTO | vi |
| LOCATION MAP | vii |
| REPORT | |
| SECTION 1 - PROJECT INFORMATION | 1 |
| SECTION 2 - ENGINEERING DATA | 8 |
| SECTION 3 - VISUAL INSPECTION | 9 |
| SECTION 4 - OPERATIONAL PROCEDURES | 11 |
| SECTION 5 - HYDRAULIC/HYDROLOGIC | 12 |
| SECTION 6 - STRUCTURAL STABILITY | 14 |
| SECTION 7 - ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES | 16 |
| APPENDIX A - INSPECTION CHECK LISTS | |
| APPENDIX B - ENGINEERING DATA | |
| APPENDIX C - INSPECTION PHOTOGRAPHS | |
| APPENDIX D - HYDROLOGIC COMPUTATIONS | |
| APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS | |



MASSABESIC LAKE DAM

Manchester, N.H.

Approx. Scale 1" = 280'



PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
MASSABESIC LAKE DAM ID# N.H. 00103

SECTION 1
PROJECT INFORMATION

1.1 General

a. Authority

Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Whitman & Howard, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of New Hampshire. Authorization and notice to proceed was issued to Whitman & Howard, Inc. under a letter of May 1, 1978 from Ralph T. Garver, Colonel, Corps of Engineers. Contract No. DACW33-78-C-0313 has been assigned by the Corps of Engineers for this work.

b. Purpose

- (1) Perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.
- (2) Encourage and prepare the States to quickly initiate effective dam safety programs for non-Federal dams.
- (3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project:

a. Location

Massabesic Lake Dam is located in Manchester, New Hampshire. The dam is 2,000 feet southwest of the natural outlet of the lake. The discharge from the dam flows into Cohas Brook, a tributary of the Merrimack River.

b. Description of Dam

The Massabesic Lake Dam is a large concrete and stone masonry dam with earth embankments. The permanent spillway crest is at elevation 248.93 ft. msl, and 18" non-failing flashboards are employed across the 100' wide spillway. A bridge across the crest carries light through traffic. A 30" diameter sluice pipe is located on the left side of the spillway through the base of the dam. A gate house leading to the water supply canal is located just beyond the end of the left embankment. It is not known if there are core walls in the earth abutments.

There is a low concrete weir structure known as The Cofferdam located at the original natural outlet of the lake. It was probably built at the same time as the dam to maintain the lake level and regulate flow during construction. It consists of a central sluiceway and low concrete walls on each side extending to high ground. The sluiceway has slots for stop logs. The majority of the structure stays submerged, as the top of the concrete is about level with the dam crest, 18" below the top of flashboards. The structure appears sturdy and serviceable and might be useable to maintain the lake level in the event draining the main dam for inspection or repairs became necessary.

c. Size Classification

Although the height of the dam is less than forty feet, the relatively large volume of impounded water places this project at the upper end of the "Intermediate" size classification.

d. Hazard Classification

Cohas Brook flows westerly from the dam, passing beneath and flowing beside I-93 at the 101/193 interchange about 3/4 mile downstream. From there it enters a flat area about 1 mile long between S. Mammoth Road and Rte. 28. Then the stream valley narrows and steepens, draining into Pine Island Pond and joining the Merrimack in a short steep drop under Rte. 3A at Goffs Falls. Sudden failure would cause much property damage and some loss of life, particularly in the Pine Island Pond area. I-93 could be inundated. In addition to the flood hazard, the water supply for the City of Manchester would be severely reduced. For these reasons, this dam is placed in the "High" hazard classification.

e. Ownership

The dam was built and is owned by the Manchester Water Works, the public water utility for the City of Manchester. The city uses Massabesic Lake as a source of drinking water.

- f. Operator - Ethan Howard, Maintenance Foreman
Manchester Water Works
281 Lincoln Street
Manchester, NH 03103
603/668-3830

g. Purpose of Dam

The dam was built to control the level of the lake and to direct water to a pump station/hydroelectric facility on Cohas Avenue. However a new water treatment plant has been constructed and the water supply function of the plant is now used only for "stand-by" service. The hydroelectric facility remains fully active.

h. Design and Construction History

In 1872, the first Water Board of the City of Manchester designated Massabesic Lake as the best source of water supply for the City, and proceeded to acquire land around the lake and rights to the water. A year later, in 1873, the present dam was constructed. The crest was designed to be 2 feet below the normal "full lake" level and flashboards were used to maintain the surface at the best practical elevation. At the same time, the pumping station on Cohas Avenue was built, which also housed the hydroelectric facility to supply some of the power for the pumps. The canal and conduits were constructed to feed water from the dam to the station.

Over the years, there have been at least four changes in the crest design and flashboard arrangements. A particularly fortunate revision was made to increase the spillway capacity in 1931. Had it not been done, the dam would probably have suffered considerable damage in the flood of March 1936. The last major change came in 1945, when the crest was rebuilt into an ogee cross section and the bridge was raised one foot. These changes made for an increase in spillway capacity.

In 1974, a new water treatment plant was constructed on another part of the lake, which relegated the water supply intake system at the dam to standby status, although the hydroelectric facility is still operating in its original capacity.

i. Normal Operating Procedure

All water not taken in at the Water Treatment Plant is allowed to flow over the spillway. During times of abundant flow, the hydroelectric plant is operated.

1.3 Pertinent Data

a. Drainage Area

The drainage area at the dam is 47 sq. mi., and is considered as "flat" terrain hydrologically. Tower Hill Pond Dam is located upstream.

b. Discharge at Damsite

- (1) Maximum known flood - 2,230 cfs, Mar., 1936
- (2) Spillway capacity at maximum pool elevation
Without permanent flashboards - 4,640 cfs
With permanent flashboards - 2,880 cfs
- (3) Discharge conduit - 30" diam., invert 226.8 capacity at maximum pool elev. - 180 cfs
- (4) Total capacity of spillway and conduit - 4,820 cfs

c. Elevation (ft. above MSL)

- (1) Top Dam - 254.52
- (2) Maximum pool-design surcharge - 253.1
(bottom stringers of bridge)
- (3) Full flood control pool - N/A
- (4) Recreation pool - N/A
- (5) Spillway crest - 248.93
- (6) Invert of discharge conduit - 226.8
- (7) Streambed at centerline of dam - Approx. 225
- (8) Maximum Tailwater - Unknown

d. Reservoir

- (1) Length of maximum pool - Approx. 25,200 ft.
- (2) Length of normal pool - Approx. 25,000 ft. (odd shape)
- (3) Length of flood control pool - N/A

e. Storage (acre - ft.)

- (1) Spillway crest - 39,500
- (2) Flood control pool - N/A
- (3) Design surcharge - 42,000
- (4) Top of Dam - 44,450

f. Reservoir Surface (acres)

- (1) Top Dam - Est. 3,000
- (2) Maximum pool - Est. 2,900
- (3) Flood control pool - N/A
- (4) Recreation pool - N/A
- (5) Spillway crest - 2,630

g. Dam

- (1) Type - Concrete and stone masonry with earth embankments and long canal with earth embankments.
- (2) Length - 500 ft. (odd shape)
- (3) Height - 27 ft.
- (4) Top width - 12 ft.
- (5) Side Slopes - Upstream vertical walls; downstream 1.5:1 approx.

- (6) Zoning - Unknown
- (7) Impervious core - Unknown
- (8) Cutoff - Unknown
- (9) Grout curtain - Unknown

h. Diversion Tunnel

There are two separate outlet systems. One is a 30" pipe located at the base of the concrete dam. It is about 40 feet long and the flow is controlled by a 36" x 60" sluice gate. The gate is controlled with a hand crank operator atop the dam and has not been operated in recent years. The submerged channel leading to the sluice gate is odd shaped and constructed of stone masonry.

The other outlet system diverts water to the pumping station and hydroelectric facility. The system consists of a 36 inch intake pipe controlled from a gatehouse, a 1470 foot long canal, a second gatehouse at the far end of the canal, and a large conduit which leads to the hydroelectric and pumping station on Cohas Avenue. The discharge from the hydroelectric plant returns to Cohas Brook below the dam. The first gate is left open continuously and the second gate is operable.

i. Spillway

- (1) Type - Concrete ogee
- (2) Length of weir - 100 ft.
- (3) Crest elevation - 248.93
- (4) Gates - 18" permanent (non-failing) flashboards
- (5) Upstream channel - lakeshore
- (6) Downstream channel - Cohas Brook streambed
- (7) General - Roadway over crest supported on 4 piers

SECTION 2 - ENGINEERING DATA

2.1 Design

There is no information available concerning the design of the dam and appurtenant structures. A few plans show repairs that have been made, but they do not show the original work.

2.2 Construction

No construction records exist from either the original construction or later additions.

2.3 Operation

A few spotty lake level records are available. However, the operation of the dam is simple and no records have been kept. Some flood records were kept.

2.4 Evaluation

- a. Availability - Poor. Few data exist.
- b. Adequacy - N/A. Evaluation must be based heavily upon visual observation.
- c. Validity - N/A.

SECTION 3 - VISUAL INSPECTION

3.1 Findings

a. General

The findings of the inspection are presented in the visual inspection checklist.

b. Dam

The face of the spillway has several vertical cracks that run nearly the entire height of the dam. These cracks were repaired with an epoxy sealant in 1975. Approximately 50 weep holes were observed in the spillway face; those that could be readily reached were from 2' to 5' deep and fairly clear. The flashboards were securely bolted to the sides of the piers and it is unlikely that they would fail from a head less than the available freeboard.

A 12' v.c. pipe was discharging water at a point on the downstream slope near the northeast abutment. The origin was not found. The water being discharged was clear. There is a large seepage area at the downstream toe near the southwest end of the dam. The stone masonry joints on the upstream face on the southwest end of the dam have missing mortar.

c. Appurtenant Structures

The Cofferdam appears in serviceable condition.

Seepage is taking place through and/or under the canal embankments near its downstream end (farthest from the dam).

d. Reservoir Area

All land around Massabesic Lake is owned by the Water Works and recreation is prohibited.

e. Downstream Channel

The channel downstream of the spillway is covered with sand, gravel, and boulders. There are trees and brush growing in the channel.

3.2 Evaluation

The seepage taking place at the toe of the embankment near the southwest end of the dam could lead to long-term instability if not remedied. The seepage from both sides of the downstream end of the canal downstream of the gated outlet could lead to long-term instability of the embankments on the sides of the canal. The footpath from the toe to the crest of the southwest embankment next to the spillway could lead to serious long-term erosion if it is not remedied. Because of the high water on the upstream face, that part of the dam could not be inspected. The portion of the face above the water showed that repair of the stone masonry points was needed.

The reason for the vertical cracks in the spillway is unclear and has not been fully investigated. Although it is reported that these cracks did not leak, and that the epoxy sealant has bonded securely, it would be prudent to find the reason for their development.

Massabesic Lake Dam is assessed to be in overall poor condition. See Section 7.

SECTION 4 - OPERATIONAL PROCEDURES

4.1 Procedures

In periods of ample water, the hydroelectric plant is operated. Otherwise all flow that is not drawn off at the water treatment plant goes over the spillway.

4.2 Maintenance

The dam has been repaired as needed, and regular clean-up operations have been performed conscientiously. However, trees have been allowed to grow on embankments.

4.3 Maintenance of Operating Facilities

The sluice gate at the dam is not operated. Its condition is unknown. The flashboards are non-failing.

4.4 Warning System

There is no formal warning system at the dam.

4.5 Evaluation

The flashboards should be converted to a failing type. The sluice gate should be operated regularly.

SECTION 5 - HYDRAULIC/HYDROLOGIC

5.1 Evaluation of Features

a. Design Data

No data exists on the original design of the dam. Criteria for spillway capacity are not known.

The 1945 spillway revision appears to have been designed to pass the 1936 flood peak flow of 2,230 cfs with a small amount of freeboard to spare, although this is not certain.

b. Experience Data

The flood of March, 1936 very nearly overtopped the dam, rising to .1 ft. above the bottom of the bridge stringers (then lower than now).

There have been numerous changes in spillway crest and flashboard configurations. Most of the changes appear to have been made with maintenance and operation practicality in mind rather than hydraulic considerations.

c. Visual Observations

The flashboards in their present state appear to be permanent (non-failing) in nature. This reduces the spillway capacity and increases the overtopping potential.

The cofferdam at the former natural lake outlet appears sturdy and serviceable. The central sluiceway invert is about 5' lower than the spillway crest.

d. Overtopping Potential

Reference is made to Appendix D for the hydrologic computations performed as a part of this report.

The probable maximum flood (PMF) for this dam is computed to be about 23,700 cfs inflow

into Massabesic Lake. The probable maximum flood is defined as the largest flood that can reasonably be expected to occur on a given stream at a selected point, or the flood that may be expected from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region.

For dams of the size and hazard classifications of Massabesic Lake Dam, the "test flood" is generally chosen as the full PMF. The test flood is that flood used to evaluate the hydraulic adequacy of a project. The test flood for Massabesic Lake Dam is selected at the full PMF.

During the PMF, the peak outflow at the dam would be about 12,600 cfs, the reduction from the peak inflow of 23,700 cfs being accounted for by the considerable surcharge storage "cushioning" effect of the lake. In its present state, the spillway capacity is 3,060 cfs, or about 24% of the test flood peak outflow. At the moment of peak outflow, the dam would be overtopped by about 3.2 feet. Whether the dam could withstand this degree of overtopping cannot be determined.

If the existing permanent flashboards were replaced with properly designed flashboards, the spillway capacity would increase to 4,600 cfs (about 37% of test flood), and overtopping height would decrease to about 1.7 feet.

SECTION 6 - STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations

The upstream face of the earthen embankment sections is a vertical masonry wall.

A paved roadway crosses on the crest of the dam.

The downstream toe of the northeast embankment section is covered with trees and brush. The downstream slope of the southwest embankment section is covered with grass. Trees and brush are growing downstream of the toe of both the northeast and southwest embankment section.

There is a large seepage area at the downstream toe near the southwest end of the dam.

Vertical cracks on the spillway face have developed in recent years. The Cofferdam appears in sound and serviceable condition.

b. Design and Construction Data

No data available. Upstream configuration of spillway structure and embankment construction are unknown.

c. Operating Records

No useful data is available. The age of the dam, and the fact that it has survived several severe floods, is a favorable indicator of basic stability.

d. Post-construction Changes

Several changes have occurred to the spillway crest. Plans of the most recent change (1945) are available. See design and construction history in Section 1.

e. Seismic Stability

This dam is in Seismic Zone 2 and hence does not have to be evaluated for seismic stability in accordance with the OEC Recommended Guidelines.

SECTION 7 - ASSESSMENTS, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition

The visual inspection indicates that Massabesic Dam is in poor condition. The major concerns regarding the longterm stability of the dam with respect to soils and geology are the seepage at the downstream toe of the embankment near the southwest end of the dam, the seepage from both sides of the downstream end of the canal through which water from the gated outlet discharges, and the presence of large trees and brush on the downstream slope of the embankment sections of the dam.

The major structural concern is the development of vertical cracks in the spillway.

The major hydraulic concern is the low spillway capacity, aggravated by non-failing flashboards.

In addition, a number of operation and maintenance procedures should be followed as outlined in 7.3.b, below.

b. Adequacy of Information

The information available is such that the assessment of the safety of the dam must be based on the visual inspection. Because of the importance of the visual inspection it is necessary that the upstream face be inspected.

c. Urgency

The recommendations and remedial measures mentioned below should be implemented within one year after receipt of this Phase I Report.

d. Necessity for Additional Inspection

Due to the lack of design and construction information, the age of the structure, and

the problems noted, it is advised that measures be taken to inspect and survey (and possibly repair) the upstream face, gates, and channel bottom.

If it is determined that drawdown is necessary, this might be possible to carry out without draining the main body of the lake by regulating the Cofferdam.

This dam should undergo a thorough inspection by a competent engineer once a year, in addition to regular observation visits by maintenance personnel.

7.2 Recommendations

The owner should retain a competent engineer with special experience in structural problems of dams to investigate the cause or causes of the vertical cracking in the spillway, and to implement a remedy if necessary.

The owner should retain a competent engineer to advise on the best method of decreasing the dam's vulnerability to damage by large floods (e.g., spillway enlargement, emergency spillway construction, armoring overtopping, etc.).

The owner should retain a competent engineer to advise on repairing the seepages at the downstream toe of the southwest end of the dam and from both sides of the canal through which water from the gated outlet discharges.

The owner should also cut the trees and brush on the downstream slope of the embankment sections of the dam and for a distance of 100 feet downstream of the dam, and should engage a competent engineer to supervise the removal of the tree roots and replacement with a proper backfill.

7.3 Remedial Measures

a. Alternatives - N/A

b. Operating and Maintenance Procedures

- (1) The owner should take necessary action to prevent further erosion of the foot-path from the toe to the crest of the southwest embankment section adjacent to the spillway.
- (2) The owner should take necessary action to repair and eliminate further erosion caused by water flowing from the pipe that discharges on the downstream slope near the northeast end of the dam.
- (3) The downstream slope of the embankment sections and an area 100 feet downstream of the dam should be maintained free of brush and trees.
- (4) The flashboard system should be replaced or modified so as to fail at a head safely under the available freeboard.
- (5) The sluice gate for the pipe through the dam should be reactivated and maintained as should all gates (and other moving parts) for the canal operation.
- (6) Round the clock surveillance should be provided by the Owner during periods of unusually high flows caused by heavy precipitation, rapid snowmelt, or other reasons. The Owner should develop a formal warning system with local officials for alerting downstream residents in case of emergency.

MASSABESIC LAKE DAM

APPENDICES

- A Visual Inspection Checklist - 9 pp.
- B Engineering Data with Index
- C Inspection Photographs with Index - 12 photos
- D Hydrologic Computations
- E Information as Contained in the National Inventory of Dams

APPENDIX A
VISUAL INSPECTION CHECK LIST
PARTY ORGANIZATION

PROJECT Massabesic Lake Dam DATE June 12, 1978*
TIME 9:00 AM start
WEATHER sunny - hot
W.S. ELEV. 250.5 U.S. not DN.S. measured
(about 1" over
flashboards)

PARTY:

- | | |
|--------------------------------|-----------|
| 1. <u>T.T. Chiang, W&H</u> | 6. _____ |
| 2. <u>J. Scott, W&H</u> | 7. _____ |
| 3. _____ | 8. _____ |
| 4. _____ | 9. _____ |
| 5. _____ | 10. _____ |

| PROJECT FEATURE | INSPECTED BY | REMARKS |
|-----------------|----------------|---------|
| 1. All features | Chiang & Scott | |
| 2. _____ | | |
| 3. _____ | | |
| 4. _____ | | |
| 5. _____ | | |
| 6. _____ | | |
| 7. _____ | | |
| 8. _____ | | |
| 9. _____ | | |
| 10. _____ | | |

Second inspection - see next page.

heck list combines observations of both inspections

VISUAL INSPECTION CHECK LIST
PARTY ORGANIZATION

PROJECT Massabesic Lake Dam

DATE July 5, 1978*

TIME 9:30 AM start

WEATHER clear, cool

W.S. ELEV. 250.0 U.S. not DN.S. measured
(about 5" below flashboards)

PARTY:

- | | |
|---------------------------------------|-----------|
| 1. <u>J. Scott, W&H</u> | 6. _____ |
| 2. <u>R. Hirschfeld, Geotechnical</u> | 7. _____ |
| <u>Engineers, Inc.</u> | 8. _____ |
| 3. _____ | 9. _____ |
| 4. _____ | 10. _____ |
| 5. _____ | |

| PROJECT FEATURE | INSPECTED BY | REMARKS |
|-----------------|--------------------|---------|
| 1. All features | Scott & Hirschfeld | |
| 2. _____ | | |
| 3. _____ | | |
| 4. _____ | | |
| 5. _____ | | |
| 6. _____ | | |
| 7. _____ | | |
| 8. _____ | | |
| 9. _____ | | |
| 10. _____ | | |

Second inspection - see previous page for details of first inspection.

PERIODIC INSPECTION CHECK LIST

OBJECT Massabesic Lake Dam DATE 6/12/78 & 7/5/78
 OBJECT FEATURE Main concrete section NAME Entire party
 SCIENCE NAME

| AREA EVALUATED | CONDITION |
|--|---|
| <u>M EMBANKMENT</u> | |
| Crest Elevation | |
| Current Pool Elevation | 250.5 on 6/12; 250.0 on 7/5 |
| Maximum Impoundment to Date | 4.27' over crest - 1936 flood |
| Surface Cracks | Five vertical cracks in spillway face - repaired with epoxy in '75 |
| Pavement Condition | Some cracking and unevenness of pavement next to south end of service bridge |
| Movement or Settlement of Crest | None |
| Lateral Movement | None |
| Vertical Alignment | OK |
| Horizontal Alignment | OK |
| Condition at Abutment and at Concrete Structures | Many stone masonry joints need repointing - some quite bad, especially at normal water line on left upstream face |
| Indication of Movement of Structural Items on Slopes | None |
| Trespassing on Slopes | Footpath from road to toe adjacent to south abutment wall. Some junk thrown in discharge channels |
| Sloughing or Erosion of Slopes or Abutments | None |
| Rock Slope Protection-Riprap Failures | Vertical stone walls around upstream area need repointing |
| Unusual Movement or Cracking at or near Toes | None |
| Unusual Embankment or Downstream Seepage | Seepage area at downstream toe of embankment near south end of dam |
| Piping or Boils | None |
| Foundation Drainage Features | None |
| Toe Drains | Outfall of 15" conc. pipe found next to base of north abutment - origin unknown |
| Instrumentation System | None |

PERIODIC INSPECTION CHECK LIST

PROJECT Massabesic Lake Dam DATE 6/12/78 & 7/5/78
 PROJECT FEATURE Embankments on both sides of main concrete section NAME Entire party
 DISCIPLINE _____ NAME _____

| AREA EVALUATED | CONDITION |
|---|---|
| <u>DIKE EMBANKMENT</u> | |
| Crest Elevation | General Notes: Downstream face of both embankments has extensive tree and shrub growth. Slope quite steep. |
| Current Pool Elevation | |
| Maximum Impoundment to Date | |
| Surface Cracks | |
| Pavement Condition | |
| Movement or Settlement of Crest | |
| Lateral Movement | |
| Vertical Alignment | |
| Horizontal Alignment | |
| Condition at Abutment and at Concrete Structures | |
| Indications of Movement of Structural Items on Slopes | |
| Trespassing on Slopes | |
| Sloughing or Erosion of Slopes or Abutments | |
| Rock Slope Protection-Riprap Failures | |
| Unusual Movement or Cracking at or near Toes | |
| Unusual Embankment or Downstream Seepage | |
| Piping or Boils | |
| Foundation Drainage Features | |
| Toe Drains | |
| Instrumentation System | |

PERIODIC INSPECTION CHECK LIST

Massabesic Lake Dam

6/12/78 & 7/5/78

PROJECT _____ DATE _____

PROJECT FEATURE _____ NAME _____

DISCIPLINE _____ NAME _____

| AREA EVALUATED | CONDITION |
|---|-----------|
| OUTLET WORKS-INTAKE CHANNEL AND INTAKE STRUCTURE | |

a. Approach Channel

None as such

Slope Conditions

Bottom Conditions

Rock Slides or Falls

Log Boom

Debris

Condition of Concrete Lining

Drains or Weep Holes

b. Intake Structure

30" sluice thru dam has gate in unknown condition (maintenance foreman declined to operate).

Condition of Concrete

Stop Logs and Slots

Gate house leading into canal:
gates always open - not exercised
in a long time

PERIODIC INSPECTION CHECK LIST

PROJECT Massabesic Lake Dam DATE 6/12/78 & 7/5/78

PROJECT FEATURE _____ NAME _____

DISCIPLINE _____ NAME _____

| AREA EVALUATED | CONDITION |
|-------------------------------------|---|
| OUTLET WORKS-TRANSITION AND CONDUIT | |
| General Condition of Concrete | Apron eroded slightly - good condition |
| Rust or Staining on Concrete | |
| Spalling | None |
| Erosion or Cavitation | Apron leads directly to natural channel. Considerable amount of trash has been thrown into channel. |
| Cracking | |
| Alignment of Monoliths | |
| Alignments of Joints | |
| Numbering of Monoliths | |

General Condition of Concrete

Apron eroded slightly - good condition

Rust or Staining on Concrete

Spalling

None

Erosion or Cavitation

Apron leads directly to natural channel.
Considerable amount of trash has been
thrown into channel.

Cracking

Alignment of Monoliths

Alignments of Joints

Numbering of Monoliths

PERIODIC INSPECTION CHECK LIST

PROJECT Massabesic Lake Dam DATE 6/12/78 & 7/5/78
 PROJECT FEATURE _____ NAME _____
 DISCIPLINE _____ NAME _____

| AREA EVALUATED | CONDITION |
|---|---|
| <u>OUTLET WORKS-OUTLET STRUCTURE AND OUTLET CHANNEL</u> | |
| General Condition of Concrete | "Outlet channel" - canal leading to gatehouse at far end. Thence a conduit to pump and hydroelectric plant on Cohas Ave |
| Rust or Staining | Gates in far gatehouse operated regularly while hydro plant is working (did not observe operation) |
| Spalling | |
| Erosion or Cavitation | |
| Visible Reinforcing | |
| Any Seepage or Efflorescence | |
| Condition at Joints | |
| Drain Holes | |
| Channel | |
| Loose Rock or Trees Overhanging Channel | None |
| Condition of Discharge Channel | Generally good. Some seepage is taking place through the canal embankments at the far (south) end, on both sides |

PERIODIC INS ECTION CHECK LIST

PROJECT Massabesic Lake Dam DATE 6/12/78 & 7/5/78
 PROJECT FEATURE Crest & Spillway Face NAME _____
 DISCIPLINE _____ NAME _____

| AREA EVALUATED | CONDITION |
|--|--|
| <u>OUTLET WORKS-SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u> | |
| a. Approach Channel | No real "approach channel" |
| General Condition | N/A |
| Loose Rock Overhanging Channel | N/A |
| Trees Overhanging Channel | N/A |
| Floor of Approach Channel | Could not inspect |
| b. Weir and Training Walls | |
| General Condition of Concrete | Normal erosion - good, considering age.* |
| Rust or Staining | None |
| Spalling | Very little |
| Any Visible Reinforcing | No (plain concrete over stone masonry) |
| Any Seepage or Efflorescence | None |
| Drain Holes | Many. Generally clear, 2'-5' deep |
| c. Discharge Channel | Spillway discharges directly to natural channel, which is considerably overgrown with trees and brush. |
| General Condition | |
| Loose Rock Overhanging Channel | |
| Trees Overhanging Channel | |
| Floor of Channel | |
| Other Obstructions | |

*Five vertical cracks - see Main Concrete Section checklist

PERIODIC INSPECTION CHECK LIST

PROJECT Massabesic Lake Dam DATE 6/12/78 and 7/5/78
 PROJECT FEATURE Bridge over crest NAME _____
 DISCIPLINE _____ NAME _____

| AREA EVALUATED | CONDITION |
|-----------------------------------|---|
| <u>INLET WORKS-SERVICE BRIDGE</u> | |
| Super Structure | Bridge has wood plank wearing surface. |
| Bearings | Bridge is in good overall condition |
| Anchor Bolts | Used for light thru traffic - est. 50 cars/day |
| Bridge Seat | |
| Longitudinal Members | |
| Under Side of Deck | |
| Secondary Bracing | |
| Deck | |
| Drainage System | |
| Railings | |
| Expansion Joints | |
| Paint | |
| Abutment & Piers | |
| General Condition of Concrete | |
| Alignment of Abutment | |
| Approach to Bridge | |
| Condition of Seat & Backwall | |

APPENDIX B
MASSABESIC LAKE DAM
INDEX TO ENGINEERING DATA

3 Plates - Plan, plus 2 sections

Letter from Whitman & Howard, Inc. about general crack
repair, 6/4/75

Letter from Manchester Water Works to N.H. Water Re-
sources Board about leakage, 3/6/75


Letter from N.H. Water Resources Board to Manchester
Water works, 2/14/75

N.H. Water Resources Board Dam Safety Inspection Report
Form, 7/26/74

Chronology of spillway changes 1873-1945

Engineer's design notes on spillway improvements of
1945


Lake levels in 1936 (showing flood of March 1936)



From Original Survey By
Whitman & Howard, July 1978.

PLAN
Scale: 1" = 40'

| | | | |
|---|--|---|-------------------|
| WHITMAN & HOWARD INC. ENGINEERS AND ARCHITECTS WELLESLEY, MASS. | | U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS. | |
| NATIONAL PROGRAM OF INSPECTION OF NON-FED.DAMS | | | |
| MASSABESIC LAKE DAM | | | |
| COHAS BROOK | | NEW HAMPSHIRE | |
| | | | SCALE 1" = 40' |
| | | | DATE AUGUST, 1978 |



SECTION A TYPICAL SPILLWAY SECTION 1" = 10'

From original survey by
Whitman & Howard, July 1978,

WHITMAN & HOWARD INC.
ENGINEERS AND ARCHITECTS
WELLESLEY, MASS.

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAM


MASSABESIC LAKE DAM

COHAS BROOK

NEW HAMPSHIRE

SCALE 1" = 10'

DATE JULY, 1978



SECTION B
TYPICAL EMBANKMENT SECTION
1" = 10'

From original survey by
Whitman & Howard, July 1978.

WHITMAN & HOWARD INC.
ENGINEERS AND ARCHITECTS
WELLESLEY, MASS.

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS

MASSABESIC LAKE DAM

COHAS BROOK

NEW HAMPSHIRE

SCALE 1" = 10'

DATE JULY, 1978

WHITMAN & HOWARD, INC.
ENGINEERS AND ARCHITECTS

June 4, 1975

Mr. Robert Beaurivage, P.E.
Manchester Water Works
281 Lincoln Street
Manchester, NH 03101

Dear Bob:

I am enclosing a method for repairing vertical cracks in a concrete gravity dam (or dams) based on the following data and assumptions:

1. The average crack width is $3/8"$ to $1/2"$ with one crack being $1"$ wide.
2. The depth of the cracks are $3"$ to $4"$.
3. The cracks are subjected to a maximum back pressure of about 25 feet of water although none are leaking and only a little dampness is present in some.
4. It is assumed the cracks are working shrinkage cracks and they do not impair the adequacy of the structure.

Crack Repair
(Refer to enclosed sketch)

1. Using a saw tooth bit, widen the crack slightly ($1/2"$ minimum width) by cutting a trim, narrow, sharp edged groove to a depth of 2-1/2 inches.

WHITMAN & HOWARD, INC.
ENGINEERS AND ARCHITECTS

2. Clean groove of chipping dust and other foreign material with an air-water jet and dry with an air jet. After cleaning, the groove may be damp but not wet.
3. Fill the rear portion of the groove with an epoxy gel (Sikadur Gel) to a depth of 1 inch.
4. Apply a polyethylene tape bond breaker to the surface of the cured gel.
5. Prime the sealant slot with Sikaflex Primer and apply a 1-component, polyurethane-base sealant (Sikaflex 1a) to the dimensions shown.
6. Fill remainder of groove with epoxy gel.
7. Tool a 1/8" wide control joint in the gel.

Use the above materials in strict accordance with the manufacturer's directions. All the products mentioned are manufactured by the Sika Chemical Co. of Lyndhurst, New Jersey.

Very truly yours,

WHITMAN & HOWARD, INC.

Anthony Chiaravelotti, P.E.
Head, Structural Department

AC/hmg

enc.



MANCHESTER WATER WORKS

281 LINCOLN ST., MANCHESTER, NEW HAMPSHIRE 03103

TEL 888-3830

ARTHUR H. ST GERMAIN
President of the Board

GILBERT L. TUSON
Clerk of the Board

CLARENCE E. FERRY, P.E.
Director and
Chief Engineer

FREDERICK H. ELWELL, P.E.
Assistant Director and
Assistant Chief Engineer

March 6, 1975

RECEIVED
L.M.M.S.
NEW HAMPSHIRE
WATER RESOURCES BOARD

Mr. George M. McGee, Sr.
Chairman
N. H. Water Resources Board
37 Pleasant St.
Concord, N. H. 03301

Subject: NHWRB Dam No. 150.06, Manchester, New Hampshire

Dear Mr. McGee:

In reply to your letter of February 14, 1975, we are pleased to furnish you with the following information.

On April 13, 1974, the subject dam was thoroughly inspected by one of our engineers. At this time, pictures of the dam were taken and a report prepared. The report noted (as did yours of July 26, 1974) that some concrete had spalled away from the face of the dam. It did not indicate however any leakage at the right (north) abutment, or for that matter, anywhere else on the face or toe of the dam. This can be substantiated by copy of the enclosed photograph and also by visits on two separate occasions later in the year with contractor representatives. If in fact flowing water appeared at the right side abutment at time of your inspection, we suggest that its origin could only have been from leaking flashboards at the top corner of the dam.

Although plans for repairs to the dam do not include any work on the abutments at this time, you may be assured that if any leakage is found it will be promptly repaired. If any additional information is required at this time, please let me know.


Very truly yours,

David Kittredge

David Kittredge, P. E.
Water Supply Engineer

DK/pp

Enc.



CRACK REPAIR

State of New Hampshire
WATER RESOURCES BOARD

87 Pleasant St.
Concord 03301

February 14, 1973

Manchester Water Works
Lincoln Street
Manchester, NH 03101

CERTIFIED MAIL

Dear Sirs:

On March 15, 1974, an engineer of the New Hampshire Water Resources Board inspected your dam located on Coburn Brook in the town of Manchester.

This dam, # 150.06 in the files of the New Hampshire Water Resources Board, is classified as a menace structure, and as such, must be maintained in a manner so that this structure does not endanger the safety of the public or become a "Dam in Disrepair" (RSA 428:1). Under the statutes, (copies enclosed for your review), this office is responsible for making these inspections periodically and seeking the dam owner's cooperation in making the required repairs.

Since the fall of 1972 the Legislature has attempted to meet its statutory obligations regarding the inspection of dams, and the Board on a priority basis has made inspections in those areas of the state having a history of the least number of inspections over the years. Our priority was to inspect as many dams as possible during times that weather conditions would allow; however, our dam inspector would take immediate action on any structure that was in critical condition. Consequently, we are presently sending out letters notifying owners of dams that certain repairs are required by this Board per the statutes mentioned above. We request that you notify us within 90 days upon receipt of this letter of your intentions as to the completion of these repairs and deficiencies noted on the attached sheet.

We thank you for your cooperation in this regard, and we will be glad to answer any further questions you may have regarding the above.

Very truly yours,

George M. McGee, Sr.
Chairman

gmmg/vak:js
enclosures
cc: Board of Selectmen

February 14, 1975

Manchester Water Works
Lincoln Street
Manchester, NH 03101

RE: REQUIRED REPAIRS TO DAM #150.06 ON COHAS BROOK, MANCHESTER, N.H.

1. Repair leakage at right abutment (facing downstream).

rd/js

N. H. WATER RESOURCES BOARD
Concord, N. H. 03301

DAM SAFETY INSPECTION REPORT FORM

own: Manchester Dam Number: 150.06
inspected by: SCB Date: 25 July 1974
ocal name of dam or water body: _____
wner: Manchester W.W. Address: _____
wner was was not interviewed during inspection.
rainage Area: _____ sq. mi. Stream: Cohas Brook
ond Area: _____ Acre, Storage _____ Ac-Ft. Max. Head 20 ± Ft.
oundation: Type _____, Seepage present at toe - Yes No Yes
pillway: Type Over-Flow, Freeboard over perm. crest: 5' 8"
Width 5 ft. @ 13', Flashboard height 1' 6"
Max. Capacity _____ c.f.s.
mbankment: Type Earth & Stone Cover Road Width 30' ±
Upstream slope 0 to 1; Downstream slope 2 to 1
outments: Type Stone, Condition: Good, Fair, Poor
ates or Pond Drain: Size 30" Capacity _____ Type Gate
Lifting apparatus Handwheel Operational condition Yes
hanges since construction or last inspection: _____
Downstream development: _____
This dam would would not be a menace if it failed.
Suggested reinspection date: _____
Remarks: Leak @ RT Abt. Sur Face Cracks on
spill way some erosion of core on spill way

| | | Top Masonry | Top Flashboard |
|------|--|--|--|
| 572 | Purchase made of Bottom of Lake And Land bordering Mill Pond, Canal, And P. Station | (Deed # 14) (called overfall) | 24" Flash |
| 573 | Original Masonry Dam Constructed. | 147.00 | 149.00 |
| 384 | Some time On or After this year the Lake Profile indicates that 30" Flashboards were used | 147.00 | 30" 149.50 |
| 122. | Top Masonry was capped to a height of 20" above the old Masonry Cap & provided with 3" Ten foot Opulways 8" deep. The 30" flashboards were a continual source of trouble. | Masonry Under Flashboards 148.80 | Top Crest of Top Flashboard 149.50 |
| 131 | Spillway Capacity increased by removing old concrete substituted for 30" Flashboards in 1922 And constructing new concrete crest on dam 20" above old masonry crest with 5 slots across top to provide for 8" Flash boards across the full width of dam Old masonry stepped face of dam was faced with and irregular battered concrete face. | 148.67 | 149.50 |
| 145 | Crest of dam was Altered from the joint under the old masonry cap stone @ Elev. 145.87 from a square crest to a curved crest. The Top of the concrete curved crest is 148.00 with 10" Flashboards. The Bridge Piers & Abutts were raised 1'0" giving a freeboard of from Elev. 148.00 to bottom of Bridge Stringer Elev. 152.77 = 4.77' Freeboard. | 148.00 | 149.50 |

Mill Dam Spillway Capacity Increase

Change Dam Spillway + Provide Canal Spillway

Summary
DATE 12-5-37

The old crest (previous to 1921?) had 30" flash board and a length of about 90'. The crest was a stone crest of the Merrimack River type. I believe this crest would discharge only 75% of a sharp crested weir.

With the maximum flood of record (1936) the water rose to 0.1' above the bottom of the bridge stringers.

$$= 151.17 + 0.1 = 151.27 - 147.0 \text{ (old crest el.)} = 4.27$$

A depth of 4.27 on a sharp crested weir would discharge 33.06 per foot @ 90' = 2980 cfs
+ x .75 = 2230 cfs. ^{use 4' height} ^{2230/50 = 44.6 cfs/sq. ft.}

Rebuild crest to obtain at least this capacity.

See sheet 4 - Rebuild with crest at 148.0 with

sloping approach as now 45' & 0.9, curved top.

This will have discharge capacity 5 to 10% more than sharp crested weir = type 2 U.S.R.S. book.

$$\text{With } h = 3.27 \quad Q = 1.05 \times 92 \times 23.4 = 2260 \text{ c.f.s.}$$

In addition get 1800 c.f.s. in canal spillway, get & RAISE the Free board, or possible Head, by raising bridge & approaches 1.0'


$$\begin{array}{r} 2260 \\ 1800 \\ \hline 2440 \text{ cfs} / \div 2.8 \text{ sq. mi} = 872 \text{ cfs per sq. mi} \end{array}$$

Previous Max Flood '36 = 31 cfs per sq. mi
Required full capacity of present spillway.

Note

Absorption capacity of lake 148.0 to 152.0 = 3.6 Billion gallons
149.5 to 152.0 = 2.3 "

HEIGHT OF WATER IN LAKE MASSA RESERVOIR
1936
(JAN TO JUNE INCL)



APPENDIX C

MASSABESIC LAKE DAM

INDEX TO INSPECTION PHOTOGRAPHS

| <u>Photo No.</u> | <u>Description</u> |
|------------------|---|
| 1 | View looking southwest across spillway. |
| 2 - 3 | Sequence of 2 photos taken clockwise from upstream of northeast abutment, showing gatehouse, southwest embankment section, and southwest end of spillway (2) northeast end of spillway and northeast embankment section (3). |
| 4 | View of remnants of timber sheeting on southeast side of canal near southwest end of canal. Entrances to gatehouse visible at top of photo. |
| 5 | View of downstream wall of gatehouse at reservoir end of canal and southwest end of dam. |
| 6 | View from southwest end of dam along roadway over crest. |
| 7 | View looking southwest along canal. Note gatehouse in background. |
| 8 | View toward downstream side of embankment on southeast side of canal near gatehouse at southwest end of canal. Bottom of six-foot rule is at surface of standing water next to toe of embankment. Reeds and other marsh plants growing at downstream toe. |
| 9 | Looking southwest along guardrails at downstream side of paved road on crest. Misalignment of guardrails appears to be due to auto accident. |


Photo No.

Description

- | | |
|----|--|
| 10 | View of spillway from toe of southwest abutment showing epoxy repairs to vertical cracks. Also note large number of weepholes. |
| 11 | Cofferdam from right side. Note submerged walls and top of sluiceway above water. Downstream is to the right. |
| 12 | Detail of cofferdam sluiceway. Depth to bottom about 6 ft. Plank partially wrecked. |



1




2



3



4



5



6



7



8



9



10



11



12

APPENDIX D
HYDROLOGIC COMPUTATIONS
WATERSHED MAP

Massabesic Lake (Built 1886, 30 ft high)

I. Hydrology & Hydraulic Data

a) Drainage Area: The total drainage area upstream of the dam is 47 sq. miles, which includes drainage areas for Tower Hill Reservoir, Clark Pond, etc.

b) Basin Slope: Along Little Massabesic Brook & Hook Brook

$$\text{Slope} = \frac{640-252}{23000} = 0.01687$$

$$\text{Along Preston Brook; Slope} = \frac{500-252}{25000} = 0.00992$$

Conclusion: Though the slope along Little Massabesic Brook & Hook Brook is little steeper than flat channel, due to there being lots of wet lands along the channels, and Tower Hill Reservoir and several small ponds located upstream of Massabesic Lake, which are all serviced as detention area, the drainage basin condition can be considered as flat area.

c) Water Surface Area: Neglecting all other reservoirs, the water area for Massabesic Lake = 2634 acres At El. 250.43 and is increased at a rate of about 100 - 150 acres per foot increase in elevation. For the purpose of estimation, use 100 acres increase per foot, increased up to 3000 acres. (Since top of dam elevation is 254.52)

| d) <u>Storage Capacity</u> | <u>U.S.G.S. Elev.</u> | <u>Area (Acres)</u> | <u>Storage (A.F.)</u> |
|----------------------------|-----------------------|---------------------|-----------------------|
| | 254.52 | 3000 Estimate | 10,024 |
| <u>Spillway Crest</u> | 250.43 | 2634 | 1310 |
| <u>Elev. = 243.33</u> | 249.33 | 2609 | 1,265 |
| | 247.43 | 2452 | 11,473 |
| | 244.43 | 2139 | 2943 |
| | 239.43 | 1333 | |



BY T.T.G. DATE Aug 78 PROJECT Army Corps Engs SHEET NO. 2 OF 9
 CHKD. BY DATE Dam Safety Inspection JOB NO. 8-085

the total storage of the top 15 ft (from top of Dam down) is about 39543 Acre-Ft. Since there was no information concerning the rest storage capacity, it is estimated as follows.


At El. 239.43 Area = 1938 Acres

" 224.43 Area = 0.0 Acres

Average = 919 Acres

Estimate storage volume for the lower portion 15 ft of the Lake = $919 \times 15 \times 1.5 = 20677.5$ Acre-Ft.

Therefore total storage = 43,220 Acre-Ft, it can be considered as intermediate storage reservoir but very close to large reservoir category.



F) Spillway Capacity.

Spillway Max. Capacity (Neglecting Wave effect)
 $= 3.6 \times 100 \times (25.5 - 24.9)^{3/2} = 4644 \text{ cfs}$

Spillway normal capacity (With 2.4 ft wave effect)
 $= 3.6 \times 100 \times (5.5 - 2.4)^{3/2} = 1765 \text{ cfs}$

Spillway Max. Capacity with Permanent Flashboard
 $= 3.6 \times 100 (5.5 - 1.5)^{3/2} = 2880 \text{ cfs}$

There are two outlet pipes, both have 3' ϕ with a capacity of 180 cfs, but one of the gates has not been operated for long time.

- g) Discharge Curve with consideration of the dam length as additional broad crest weir; length = 1000', $L=2.7$.
 (Assume overtopping will not cause dam failure, but this is not to suggest that an earth dam can be overtopped. The first rule for earth embankment design is that this shall not be overtopped.)

For Water Surface At Top of Dam $Q_D = 4644 + 180 = 4824 \text{ cfs}$

For Water Surface At 1 ft above Dam $Q_D = 180 + 3.6 \times 100 \times 6.5^{3/2} + 2.7 \times 1000 = 8846 \text{ cfs}$

For Water Surface At 4 ft above Dam

$Q_D = 180 + 3.6 \times 100 \times 9.5^{3/2} + 2.7 \times 1000 (4)^{3/2}$
 $= 180 + 10541 + 21600 = 32321 \text{ cfs}$

For Water 3 ft overtopping $Q_D = 180 + 3.6 \times 100 \times 8.5^{3/2} + 2.7 \times 1000 (3)^{3/2}$
 $= 180 + 8921 + 14030 = 23131$

If the permanent flashboard will stay, then the capacity will reduce correspondingly

Water At Top of Dam $Q_D = 2880 + 180 = 3060 \text{ cfs}$

1 ft above Top of Dam $Q_D = 4035 + 180 + 2700 = 6905 \text{ cfs}$

4 ft above Top of Dam $Q_D = 8146 + 180 + 21600 = 29926 \text{ cfs}$


3 ft above Top of Dam $Q_D = 20877 \text{ cfs}$



BY T.T.C. DATE 7-2-59
 CHKD. BY DATE

PROJECT Army Corps Flood
Dam Safety Inspection - Macombesic

SHEET NO. 4 OF 9
 JOB NO. 8-085



h.) Estimated Peak Probable Maximum Flood inflow = 505 cfs/sq. mi.

i.) Neglecting Tower Hill Reservoir and other small Pond storage effect.
 Peak inflow = $505 \times 47 = 23,735$ CFS

Spillway maximum capacity = $4644 / 23735 = 20\%$ of Peak inflow.

ii.) Considering Tower Hill Reservoir storage effect.

Due to the adequate spillway capacity of Tower Hill Reservoir, the effect of storage does not affect the peak inflow rate, since when considering a small watershed area, the runoff rate per unit watershed area becomes higher, so is the inflow. Therefore the peak P.M.F. = 23740 CFS



i) Estimating Effect of Surge Storage in PMF Pond.

(i) Assume Perm. Flashboard Will be remove, for $Q_{P1} = 23740$ cfs.

$$H_1 = 257.1 - 249 = 8.1 \quad \text{From Discharge rating curve}$$

$$\begin{aligned} \text{STOR}_1 &= 8.1 \times 3000 \times 1.563 \times 10^{-3} \times 12 / 47 \\ &= 9.70 \text{ inch} \end{aligned}$$

$$Q_{P2} = Q_{P1} \left(1 - \frac{9.70}{19}\right) = 11624 \text{ cfs}$$

$$H_2 = 256.0 - 249 = 7.0 \text{ ft}$$

$$\text{STOR}_2 = 7.0 \times 3000 \times 0.001563 \times 12 / 47 = 8.37 \text{ inch}$$

$$\text{STOR}_{\text{ave}} = \frac{9.7 + 8.37}{2} = 9.24 \text{ inch}$$

$$Q_{P3} = Q_{P1} \left(1 - \frac{9.04}{19}\right) = 12,448 \text{ cfs}$$

$$H_3 = 256.3 - 249 = 7.3 \text{ ft}$$

$$\begin{aligned} \text{STOR}_3 &= 7.3 \times 3000 \times 0.001563 \times 12 / 47 \\ &= 9.4 \text{ in} \end{aligned}$$

$$Q_{P4} = Q_{P1} \left(1 - \frac{9.4}{19}\right) = 11,939 \text{ cfs}$$

$$H_4 = 256.10 - 249 = 7.1$$

$$\begin{aligned} \text{STOR}_4 &= 7.1 \times 3000 \times 0.001563 \times 12 / 47 \\ &= 8.45 \text{ in} \end{aligned}$$

$$\text{STOR}_{\text{ave}} = \frac{8.45 + 9.4}{2} = 8.92 \text{ inch}$$

$$Q_{P5} = Q_{P1} \left(1 - \frac{8.92}{19}\right) = 12591 \text{ cfs} \quad \text{say } 12,600 \text{ cfs}$$

$$H = 256.2 - 249 = 7.2 \text{ ft} \quad \text{Overtopping } 1.7 \text{ ft}$$

(ii) If Perm. Flashboard Will not be removed

$$H_1 = 257.8 - 249 = 8.8 \text{ ft}$$



$$STOR1 = 8.8 \times 12 \times 3000 \times 1.553 / 47000 = 10.54 \text{ inch}$$

$$QP2 = 23740 (1 - \frac{10.54}{17}) = 10575 \text{ cfs}$$

$$H_2 = (256.2 - 249) = 7.2 \text{ ft}$$

$$STOR2 = 7.2 \times 12 \times 3 \times 1.553 / 47 = 8.62 \text{ in}$$

$$STOR_{ave} = \frac{8.62 + 10.54}{2} = 9.58 \text{ in}$$

$$QP3 = 23740 (1 - \frac{9.58}{17}) = 11,770 \text{ cfs}$$

$$H_3 = 256.35 - 249 = 7.35 \text{ ft} \approx 7.2 \text{ ft}$$

$$\text{Use } H_3 = 7.4 \text{ ft}$$

So it is about 3.2 to 3.5 ft overtop the earth embankment.

The existing earth embankment and the section of roadway, which have (above) same elevation and have all been considered as broadcrest weir if overtopped, are not in very good condition, especially, the main dam. The design and construction data for the dam could not be found; the fills of the dam therefore are unknown. The reservoir is intermediate in size, but has a large water surface area; if the dam fails, with a city of Manchester near the downstream, the hazard would be very high.

Therefore, increasing the spillway capacity, is necessary.

j) Improvement =

There are several possible ways to increase the spillway capacity.

1) By raising the dam, which does not seem economical, because the height has to be raised by over 10 ft., and the length may be too long. Detail survey of the Lake shore



would be necessary to determine the total volume needed for raising the dam and determination of the cost would be needed. Flashboard should be converted to failure type, at higher head, so to provide additional capacity if flood caused by hurricane, waves, with their effects, resulted.

- 2) increase existing spillway length at Dam
 try 300' Ogce Spillway

$$H = \left(\frac{23740}{300 \times 3.6} \right)^{0.667} = 7.85 \text{ Ft}$$

$$\text{STOR}_1 = \frac{7.85 \times 3000 \times 12 \times 1.563}{47000} = 9.39 \text{ inch}$$

$$\text{QP}_2 = 23735 \times \left(1 - \frac{9.39}{19} \right) = 12000 \text{ cfs}$$

$$H_2 = \left(\frac{12000}{300 \times 3.6} \right)^{0.667} = 4.98 \text{ Ft}$$

$$\text{STOR}_2 = \frac{4.98 \times 9.39}{7.85} = 5.96 \text{ inch}$$

$$\text{STOR}_{\text{ave}} = \frac{5.96 + 9.39}{2} = 7.675 \text{ inch}$$

$$\text{QP}_3 = 23735 \left(1 - \frac{7.675}{19} \right) = 14,147 \text{ cfs}$$

$$H = \left(\frac{14147}{300 \times 3.6} \right)^{0.667} = 5.56 \text{ Ft} < 5.59 \text{ Ft gross freeboard}$$


- 3) Wave height.

Direct water surface straight length toward dam
 = 1750 ft = 0.033 stat. mile = F

Using 80 mile/hr = V

$$h_w = 0.17 \sqrt{VF} + 2.5 - \sqrt{F} = 0.44 + 2.5 - .54 = 2.40 \text{ Ft (max.)}$$

therefore actual length of spillway would have to be



much larger or a masonry wall for wave protection should be constructed, if wave effect is considered

- 4) Convert Lake Shore Road with box culverts as emergency spillway. The box culverts may have invert elevation of 248.5 with 2 ft flashboard

Using 1.0 ft for wave protection, so max. water level would, at elev. 253.5 (Additional wave protection could be added by stone wall)

Spillway Crest El. 248.93
 $H = 4.57$ ft

Spillway Capacity = $3.6 \times 100 \times (4.57)^{3/2}$
 = 3517 cfs say 3500 cfs.

with surcharge effect, the NPF = 15000 cfs

Emergency Spillway Capacity = 11,500 cfs

Use Broad weir $C = 3.0$ $H = 253.5 - 248.5 = 5.0$

$Q = CBH^{3/2}$ $B = \frac{11500}{3 \times 11.18} = 342$ ft in length

h) Conclusion:

1. Hydraulically, the spillway length is too short. It only can discharge about 20% of the estimated PMF peak inflow.
2. there are several alternatives to increase the capacity of the spillway; by raising the dam earth embankment section, by constructing additional spillway, or by the combination. But detail analysis should be carried through, before any design and construction changes are made.
3. there is an exist masonry cofferdam about 900 ft upstream of the existing dam. The cofferdam is still in fair condition. Therefore, it serves as a safety factor; so, an emergency alarming system could



be installed, if anything happened to the dam, using the cofferdam to protect, a complete loss of the reservoir may save much damage.

4. The present spillway already has cracked. Due to the high water level, the actual condition of the spillway, especially upstream, can not be inspected, therefore, break the cofferdam and drain the small ponding area between the cofferdam and the dam to have a detailed inspection for the planning of spillway capacity expansion.
5. The actual length of the spillway should be determined by detailed flood routing method, since the cost-benefit analysis should be determined. We all like to see a super-safe construction, but economically, it may not be a good design.
6. The upstream face stone wall (riprap) is in fair to poor condition; maintenance of the riprap stone wall should be done when draining the small pond between cofferdam & main dam.



WATERSHED AREA
MASSABESIC LAKE DAM

SCALE 1"=62,500

U.S.G.S. QUARD. SHEETS-
(MANCHESTER, N.H. & SUNCOOK, N.H.)



APPENDIX E
INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS



INVENTORY OF DAMS IN THE UNITED STATES

| STATE | IDENTITY NUMBER | DIVISION | STATE | COUNTY | CONGR DIST. | STATE | COUNTY | CONGR DIST. | NAME | LATITUDE (NORTH) | LONGITUDE (WEST) | REPORT DATE |
|-------|-----------------|----------|-------|--------|-------------|-------|--------|-------------|---------------------|------------------|------------------|-------------|
| NH | 103 | NED | NH | 011 | 01 | | | | MASSABESIC LAKE DAM | 4257.8 | 7125.7 | 15AUG78 |

| POPULAR NAME | NAME OF RESERVOIR |
|--------------|-------------------|
| | MASSABESIC LAKE |

| REGION | BASIN | RIVER OR STREAM | NEAREST DOWNSTREAM CITY-TOWN-VILLAGE | DIST FROM DAM (MI.) | POPULATION |
|--------|-------|-----------------|--------------------------------------|---------------------|------------|
| 01 | 05 | COMAS BROOK | MANCHESTER | 1 | 87800 |

| TYPE OF DAM | YEAR COMPLETED | PURPOSES | STRUCTURAL HEIGHT (FT.) | HYDRAULIC HEIGHT (FT.) | IMPOUNDING CAPACITIES | |
|-------------|----------------|----------|-------------------------|------------------------|-----------------------|-------------------|
| | | | | | MAXIMUM (ACRE-FT.) | NORMAL (ACRE-FT.) |
| CITRAG | 1873 | S | 28 | 27 | 56000 | 44500 |

DIST OWN FED R PRV/FED SCS A VER/DATE
NED N N N N 04AUG78

| REMARKS |
|---------|
| |

| (7) | (8) | (9) | (10) | (11) | (12) | (13) | (14) | (15) | (16) | (17) | (18) | (19) | (20) | (21) | (22) | (23) | (24) | (25) |
|-----|--------------|------|-------------|-------------------------|--------------------|----------------|---------------|------------------|--------------|-------------|--------------|-------------|--------------|-------------|--------------|-------------|--------------|-------------|
| D/S | SPILLWAY | | | MAXIMUM DISCHARGE (FT.) | VOLUME OF DAM (CY) | POWER CAPACITY | | NAVIGATION LOCKS | | | | | | | | | | |
| HAS | CREST LENGTH | TYPE | WIDTH (FT.) | | | INSTALLED (MW) | PROPOSED (MW) | NO. | LENGTH (FT.) | WIDTH (FT.) | LENGTH (FT.) | WIDTH (FT.) | LENGTH (FT.) | WIDTH (FT.) | LENGTH (FT.) | WIDTH (FT.) | LENGTH (FT.) | WIDTH (FT.) |
| 1 | 500 | C | 100 | 2260 | 7500 | 4 | | | | | | | | | | | | |

| OWNER | ENGINEERING BY | CONSTRUCTION BY |
|------------------------|----------------|-----------------|
| MANCHESTER WATER WORKS | | |

| REGULATORY AGENCY | | | |
|-------------------|-----------------|-----------------|-----------------|
| DESIGN | CONSTRUCTION | OPERATION | MAINTENANCE |
| NH WATER RES BD | NH WATER RES BD | NH WATER RES BD | NH WATER RES BD |

| INSPECTION BY | INSPECTION DATE | AUTHORITY FOR INSPECTION |
|------------------|-----------------|--------------------------|
| WHITMAN + HOWARD | 12 JUN 78 | PL 92-367 |

| REMARKS |
|---------|
| |